AWARD

CITY OF FORT LAUDERDALE

PROCUREMENT DEPARTMENT
100 N. ANDREWS AVENUE, 6TH FLOOR
FORT LAUDERDALE, FL 33301
(954) 828-5140

City Commission Approval:	**Period Covered:**	**Contract No.:**
Memorandum No. 04-1313	10/01/04 – 09/30/07	552-9075

Vendor: **MBE_** **WBE__**
Business Informations Systems
Suite 300
1350 NE 56 Street
Fort Lauderdale, FL 33334

Attn: Steve Coldren
954-493-7377
Fax: 954-493-6541
Email: scoldren@bisdigital.com

Invoice To:
City of Fort Lauderdale
Accounts Payable
100 N. Andrews Avenue
Fort Lauderdale, FL 33301

Payment Terms: Net 30
Delivery: 3 Business Days

****

AUDIO VISUAL SERVICES FOR PUBLIC ADDRESS SYSTEMS

See attached pricing proposal pages.

Insurance Coverage Required: Yes X No _
Authorized for Purchases: Under $25,000 X Over _
Extension Options: Yes X No _ Years: 3

We hereby accept this award and all terms, conditions, and specifications of the bid referenced, Bid No.552-9075.

Authorized Signature and Title Date

Printed Name and Title

****

Department Contract Co-Ordinators:
Gary Gray, Information Technical Services, 954-828-5762
Donna Varisco, City Clerk's Office, 954-828-6313
Marisol DiBernardo, Fire Rescue Communications, 954-828-6385

Procurement Specialist:
Linda R. Wilson, C.P.M., CPPB, 954-828-5146

Kirk W. Buffington, C.P.M.
Director of Procurement Services

Item No.	Estimated Annual Quantity	Description	Manufacturer and Model	Unit Material Cost	Unit Labor Cost
1	500 ft.	Plastic Jacket 18 ga. twisted pair cable, Installed – 50 foot estimated run length.		per ft. $.11	$60
2	200 ft.	Plastic Jacket 18 ga. twisted pair Shielded cable, Installed – 50 foot estimated run length.		per ft. $.16	$60
3	5	ValCom Integrated speaker/amplifier	V1010C	$39.98	$30
4	2	ValCom Power Supply for above unit		$24.00	$30
5	10	Horn type PA speaker, 70-volt operation, 6" diameter, and 10-watt minimum. Installed.	ATLAS EA15T	$46.98	$30
6	10	Horn type PA speaker, 70-volt operation, 12" diameter, and 30-watt minimum. Installed.	ATLAS AFX40TN	$98.00	$30
7	10	Cone type PA speaker, 70-volt operation, 6" diameter, in wall mount housing. 10 watt minimum. Installed.	ATLAS 8" SM82	$219.00	30
8	10	Cone type PA speaker, 70-volt operation, 6" diameter, in ceiling mount housing. 10 watt minimum. Installed.	ATLAS FA136T87	$53.00	$30
9	5	Cone type PA speaker, 70-volt	NEXT	PAGE	

		operation, 8" diameter, in wall mount housing. 10 watt minimum. Installed.	BOGEN WBS810T725	$75	$30
10	5	Cone type PA speaker, 70-volt operation, 8" diameter, in ceiling mount housing. 10 watt minimum. Installed.	ATLAS FA138T87	$65	$30
11	5	Cone type PA speaker, 70-volt operation, 10" diameter, in wall mount housing. 10 watt minimum. Installed.	SM82T 8"	$219	$30
12	5	Cone type PA speaker, 70-volt operation, 10" diameter, in ceiling mount housing. 10 watt minimum. Installed.	VALCOM V1060A 8"	$39	$30
13	2	Desk Microphone – for Fire Stations. See specifications in Section 5.3.4. Installed.	SHURE 550L	$101.60	$15
14	1	Shure SM-57 Microphone. See specifications in Section 5.3.4		149.00	
15	1	Shure SM-81 Microphone. See specifications in Section 5.3.4		529.00	

Item No.	Estimated Annual Quantity	Description	Manufacturer and Model	Unit Material Cost	Unit Labor Cost
16	1	ElectroVoice ND267A Microphone. See specifications in Section 5.3.4		119.00	
17	1	ElectroVoice RE-20 Microphone. See specifications in Section 5.3.4		449.00	
18	6ea	70-volt transformer with multiple power taps. Installed.	ATLAS HT 167	$8.25	$15
19	1ea	Public Address Amplifier, 100 watt. See detailed specifications in section 5.3.1. Installed.	PEAVEY UMA 1502	$650	$30

Item No.	Estimated Annual Quantity	Description	Unit Labor/ hourly	EST. Annual Labor Cost
20	33 hrs	Labor – City Commission/Special Meetings; Monday through Friday. Set-up, test, standby, repair service of equipment.	$60	$1980
21	As needed	Labor, Regular hours – 8:00AM to 5:00PM Monday through Friday. For installation of cables, accessories, and repairs not included above.	$60	N/A
22	25 hrs	Labor, Overtime. For City Commission Meetings/Special Meetings for repair service of equipment. Other than standard hours.	$75	$1875
23	As needed	Labor, Overtime. For installation of cables and accessories not included above. Other than standard hours, above items.	$75	N/A
24		Material purchase discount level	10 %	